Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work : Improvements to Drain at Vijayalakshmi Layout at Bagalagunte in Ward no. 14

SNo	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Sri. J.C Ramachandra	
				In Figures (Rs)	In Words (Rs)
1	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH /Chapter 3 (Page No.142, Item No. 19.1)	Cum	113.75	91.48	Rupees Ninty One and Fourty Eight Paisa Only
2	Removing B.S slab of Drain and stacking (Page No.25, Item No. 5.32)	Sqm	143.10	69.17	Rupees Sixty Nine and Seventeen Paisa Only
3	KSRB 4 - 1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.3)	Cum	35.78	5429.87	Rupees Five Thousand Four Hundred Twenty Nine and Eighty Seven Paisa Only
4	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 7.5 cms thick (Page No.25, Item No. 5.31.1)	Sqm	572.40	700.63	Rupees Seven Hundred Twenty and Sixty Thiree Paisa Only
5	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.13, Item No. 4.7)	Cum	39.75	5892.86	Rupees Five Thousand Eight Hundred Ninety Two and Eighty Six Paisa Only
6	KSRB 5-14.1 : Providing and construction load bearing wall with solid concrete block of Size 400x200x200mm having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges scaffolding, curing, hire charges of machineries etc., Complete as specification(Page No.25, Item No. 5.27.1)	Sqm	212.00	1045.36	Rupees One Thousand and Fourty Five and Thirty Six Paisa Only

Ramachandra
Signature of Contractor

Executive Engineer

Scanned by CamScanner

7	Supplying and fixing precast reinforced conceret slabs 10cm thick of mix M20 using 20mm and sownsize graded grantite metal using reinforecement 100mm dia steel at 150mm C/C both ways cost, transportation, hire charges of machinerym machine cutng the vertical face to get plain even surface etc., complete with all lead and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	477.00	1787.15	Rupees One Thousand Seven Hundred Eighty Seven and Fifteen Paisa Only
8	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm (Page No.25, Item No. 5.29.1)	No.s	1177.78	406.10	Rupees Four Hundred and Six andTen Paisa Only
9	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. (Page No.122, Item No.15.80)	Sqm	238.50	29.01	RupeesTwenty Nine and One Paisa Only
10	KSRB 15-19.2 : Providing and applying spary painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materiasl, labour, complete as per specifications. (Page No.122, Item No.15.81)	Sqm	238.50	73.63	Rupees Seventy Three and Sixty Three Paisa Only
11	KSRRB 300-52.1 : Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications. MORTH specifications No.305.4.3 (Page No.148, Item No. 19.58)	Sqm	1377.00	22.31	Rupees Twenty Two and Thirty OnePaisa Only
12	KSRB 4 - 1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.3)	Cum	201.15	5429.87	Rupees Five Thousand Four Hundred Twenty Nine and Eighty Seven Paisa Only

EXECUTIVE ENGINEER

Bruhat Bangalore [illegible] Palike

Dasarahalli Zone, Bangalore-57.

Executive Engineer

Ramachandra

Signature of Contractor

Scanned by CamScanner

13	Cement Concrete Pavement:- Construction un-reinforced plain cement concrete pavement, thickness as per design over a prepared sub base with OPC cement or any other type as per clause 1051.2.2. with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrance, sealant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grades as per drawing complete as per specifications. M20 (at 300 kg per cum coarse aggregate @ 0.64 cum and fine aggregate @ 0.43 cum) (Page No.177, Item No. 22.6.2)	Cum	206.55	5798.03	Rupees Five Thousand Seven Hundred Ninty Eight and Three Paisa Only
14	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift (Page No.178, Item No. 22.7)	Cum	1377.00	100.41	Rupees One Hundred and Fourty One Paisa Only
15	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement (Page No.178, Item No. 22.8.1)	Rmtr	418.50	128.30	Rupees One Hundred Twenty Eight and Thirty Paisa Only
16	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4KM a) Basic rate for haulage of materials as per item No. 17.4/ KSRRB: M100-4,1 ... Rs. 2.00 Tonne / Km b) Average earth of work 1.28 Tonne / Km Rs, 2.00 c) Add loading and unloading Page. No. 133 Item No. 17.1 PWD SR 2016-17	Cum	790.00	90.15	Rupees Ninty and Fifty Paisa Only

Executive Engineer,
Dasarahalli Division

Signature of the Contractor

Ramachandu
Signature of Contractor

Executive Engineer

Scanned by CamScanner